



**GOVERNMENT COLLEGE OF ENGINEERING, KARAD.**  
Vidyanagar, Karad 415 124. Tal: Karad, Dist: Satara, Maharashtra, India.

Phone No. : ( 02164) 274066, 271711, 272414, 272415) Fax No. : ( 02164 )  
271713 Email: geek \_ brns@yahoo.co.in

No. CEK/QUOT/Old Parking Shed/2019-20/ 3838

Date: - 13 NOV 2019

To,

13 NOV

13 NOV 2019

**Sub: - : Providing Parking Shed to E and F Quarters using old parking shed material and painting of Basket Ball Court at GCE, Karad**

Dear Sir,

With reference to the above, I request you to please quote your most comparative rates for the work as detailed overleaf/enclosed so as to reach the office **on or before 25/11/2019**. The prices of the **work should be quoted to G.C.E., KARAD** and exclusive of all taxes. The delivery period should be stated clearly and adhered to 'AF' or 'D' forms will be supplied where necessary. The R.R. through Bank or V.P. will not be accepted if order is placed. The specification of the material should be mentioned in full such as brand, make and company etc. I do not bind myself to accept/reject the offer, and its detailed leaflet must be attached. Your quotation should be valid at least for 30 days from the date of opening. The quotations should be sent in a sealed envelope. The envelope should please be superscripted with words **'QUOTATION DUE ON – Principal, Govt. College of Engg. Karad'**

With this office reference no. & date of opening should also be mentioned on the sealed envelope. If the materials are not supplied according to the specification, it will be returned to you at your own cost. If ordered, you will have to submit three copies of the bill, which will be passed after receipt of material in good condition. Please note that if there is any overwriting in the quotation, the said item will not be taken in to consideration unless is initialed.

**The quotations should be received on or before: - 25/11/2019 on or before 4-00 pm.**

**The quotation received will be opened on: - 25/11/2019, at 5-00 pm.**

**'QUOTATION – Principal, Govt. College of Engg. Karad'****RECAPITULATION SHEET**

**Name of Work: - Providing Parking Shed to E and F Quarters using old parking shed material and painting of Basket Ball Court at GCE, Karad**

<b>SUMMARY SHEET</b>		
<b>Sr. No.</b>	<b>Item Description</b>	<b>Amount</b>
1	Work Portion	265777.00
	ADD GST 12%	31893.24
	<b>TOTAL WITH GST</b>	<b>297670.24</b>
	<b>Say</b>	<b>297670.00</b>


**Abstract Sheet**

<b>Sr. No.</b>	<b>SSR 2019-20 Item No.</b>	<b>Item Description</b>	<b>Qty</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>
1	38.26 Pg. No. 300	Removing G.I. or A.C. sheet roofing including purlins, principal rafters etc. including sorting serviceable and unserviceable materials, stacking the same as and where directed in the compound including scaffolding etc. complete.	60.00	Sqm	71.00	4260.00
2	38.27 Pg. No. 301	Removing and lowering the roof truss carefully without damaging the members and stacking as and where directed in the compound including scaffolding etc. complete.	14.00	Nos	620.00	8680.00
3	21.02 Pg. No. 187	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means	11.04	Cum	157.00	1733.28
4	21.06 Pg. No. 187	Excavation for foundation in hard murum including removing the excavated material upto distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m) By Mechanical Means	11.04	Cum	172.00	1898.88



5	21.37 Pg. No. 191	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete.	19.50	Cum	440.00	8580.00
6	24.08 Pg. No. 218	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	2.76	Cum	5179.00	14294.04
7	24.10 Pg. No. 227	Providing and laying Cast in situ/Ready Mix cement concrete in M20 of trap/ granite/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	20.50	Cum	5456.00	111848.00
8	MARKET RATE	Fixing of structural steel work as per directed by Engineer Incharge including erecting, fixing in position etc. complete (Market Rate)	15.00	M.T.	500.00	7500.00

9	23.03 Pg. No. 223	Providing structural steel work in single stanchions composed of R.S.J. Channel etc. with caps, bases, mild steel plated, angle brackets, cleats, gusset plates, anchor bolts etc. as per detailed designs and drawings or as directed including cutting, fabrication, hoisting, erecting fixing in position, making riveted/ bolted/ welded connection and one coat of anticorrosive paint and over it two. coats of oil painting approved quality and shade etc. complete.	0.399	M.T.	70819.00	28256.78
10	38.04 Pg. No. 297	Providing and fixing corrugated galvanised iron sheets of 0.63mm thick (24 B.W.G.) for roofing without wind tiles including fastening with galvanised iron screws and bolts, lead and bitumen washers as per drawing etc. complete.(Weight of 5.5 kg/sq.m.). (Labour rate only)	130.00	Sqm	94.00	12220.00
11	38.04 Pg. No. 297	Providing and fixing corrugated galvanised iron sheets of 0.63mm thick (24 B.W.G.) for roofing without wind tiles including fastening with galvanised iron screws and bolts, lead and bitumen washers as per drawing etc. complete.(Weight of 5.5 kg/sq.m.). (Completed Item)	20.00	Sqm	733.00	14660.00
12		Providing and applying two coats of lead/zinc base oil paint/ bituminous paint of approved colour to old/ new structural steel work and iron work in buildings including scaffolding if necessary, cleaning and preparing the surface etc. complete.		Lumpsum		3000.00
13		Providing and fixing all types of screws,nuts bolts fixtures with all lead lifts completely etc.		Lumpsum		3000.00
14	MARKET RATE	Providing and applying two coats with gap of two hours of smart colours floor coat high quality antiskid water based Emulsion paint for interior and exterior concrete surfaces of approved colour including cleaning, preparing the surface and watering the surface for two days if necessary (excluding primer coat) etc. complete.	436.63	Sqm	105.00	45846.15
		<b>TOTAL AMOUNT</b>				<b>265777.13</b>
		<b>SAY</b>				<b>265777.00</b>

  
Principal,  
13/11/19

Govt. College of Engineering, Karad.