



Phone. No. (02164) 272414, 8275706613
Web : <http://gcekarad.ac.in>
Email: principal@gcekarad.ac.in,
principal.gcekarad@dtmaharashtra.gov.in

Govt. of Maharashtra
GOVT. COLLEGE OF ENGINEERING, KARAD
(An Autonomous Institute of Govt. of Maharashtra)
Vidyanagar, Karad -415124 Dist.- Satara

GCEK/QUOT/Fixing Paver Blocks/2023-24/1842

Date:- 21 APR 2023

To,

Sub: - Fixing of paving blocks in front of PG Building and near EnTC Building at GCE, Karad

Dear Sir,

With reference to the above, I request you to please quote your most comparative rates for the work as detailed overleaf/enclosed so as to reach the office **on or before 02/05/2023**. The prices of the **work should be quoted F.O.R. at G.C.E., KARAD** and exclusive of all taxes. The delivery period should be stated clearly and adhered to 'AF' or 'D' forms will be supplied where necessary. The R.R. through Bank or V.P. will not be accepted if order is placed. The specification of the material should be mentioned in full such as brand, make and company etc. I do not bind myself to accept/reject the offer, and its detailed leaflet must be attached. Your quotation should be valid at least for 30 days from the date of opening. The quotations should be sent in a sealed envelope. The envelope should please be superscripted with words **'QUOTATION DUE ON – Principal, Govt. College of Engg. Karad'**

With this office reference no. & date of opening should also be mentioned on the sealed envelope. If the materials are not supplied according to the specification, it will be returned to you at your own cost. If ordered, you will have to submit three copies of the bill, which will be passed after receipt of material in good condition. Please note that if there is any overwriting in the quotation, the said item will not be taken in to consideration unless is initialed.

Government registered contractors are only eligible to fill the quotations.

The quotations should be received on or before: - 02/05/2023 on or before 3:00 pm.

The quotation received will be opened on: - 03/05/2023 after 11.00 am.

‘QUOTATION – Principal, Govt. College of Engg. Karad’

**Name of Work: - Fixing of paving blocks in front of PG Building and near EnTC Building at
GCE, Karad**


SUMMARY SHEET

Sr. No.	Description	Amount
	Total Civil Work	Rs. 1,05,910.00
	Add GST 18%	Rs. 19,064.00
	Total with GST	Rs. 1,24,974.00

ABSTRACT (As per SSR 2022-23)

Sr. No.	Item Ref.	Item Description	Qty	Unit	Rate in Rupees	Amount
1	21.01 Pg. No. 153	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m.) By Manual Means	5.00	Cum	239.00	1195.00
2	21.37 Pg. No. 157	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete.	16.11	Cum	599.00	9649.89
3	2.31 Pg. No. 25	Compacting the hard murum side widths including laying in layers on each side with vibratory roller including artificial watering etc. complete.	318.60	Sqm	21.00	6690.60
4	27.12 Pg. No. 198	Providing fly ash brick masonry with conventional/ I.S. type fly ash bricks in C.M. 1:6 in foundation and plinth including bailing out water manually striking joints, racking out joints watering and scaffolding etc. complete. Completed Item Rate = 6884/ Cum Fly Ash Brick = (500 x 7) = 3500/ Cum Total Rate without brick = 3384/ Cum	6.64	Cum	3384.00	22469.76
5	32.11 Pg. No. 209	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 Kilogram per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.	32.09	Sqm	639.00	20505.51
6	33.53 Pg. No. 219	Providing and fixing heavy duty inter locking concrete RUBBER MOULD GLOSSY PAVING BLOCKS of 60 millimeter thickness of having a strength of 400 Kilogram/sq.m of approved quality and shape on a bed of crushed sand of 25 to 30 millimeter thick including striking joints and cleaning etc. complete. (using 100% crushed sand) Completed Item Rate = 1096/ Sqm Paving block material rate = 734/ Sqm Total Rate without block = 362/ Sqm	111.60	Sqm	362.00	40399.20

Sr. No.	Item Ref.	Item Description	Qty	Unit	Rate in Rupees	Amount
7		Other repairs works if any		LS		5000.00
		TOTAL AMOUNT				105909.96
		SAY				105910.00


Principal,
Govt. College of Engineering, Karad