



Phone. No. (02164) 272414, 8275706613
Web : <http://gcekarad.ac.in>
Email: principal@gcekarad.ac.in,
principal.gcekarad@dtmaharashtra.gov.in



Govt. of Maharashtra
**GOVT. COLLEGE OF ENGINEERING,
KARAD**

(An Autonomous Institute of Govt. of Maharashtra)
Vidyanagar, Karad -415124 Dist.- Satara

GCEK/QUOT/Two wheeler parking /2021-22/215.

Date:-15/01/2022

To,

Sub: - Providing Concrete parking for two wheeler work at GCE,

Dear Sir,

With reference to the above, I request you to please quote your most comparative rates for the work as detailed overleaf/enclosed so as to reach the office **on or before 25/01/2022**. The prices of the **work should be quoted F.O.R. at G.C.E., KARAD** and exclusive of all taxes. The delivery period should be stated clearly and adhered to 'AF' or 'D' forms will be supplied where necessary. The R.R. through Bank or V.P. will not be accepted if order is placed. The specification of the material should be mentioned in full such as brand, make and company etc. I do not bind myself to accept/reject the offer, and its detailed leaflet must be attached. Your quotation should be valid at least for 30 days from the date of opening. The quotations should be sent in a sealed envelope. The envelope should please be superscripted with words **'QUOTATION DUE ON – Principal, Govt. College of Engg. Karad'**

With this office reference no. & date of opening should also be mentioned on the sealed envelope. If the materials are not supplied according to the specification, it will be returned to you at your own cost. If ordered, you will have to submit three copies of the bill, which will be passed after receipt of material in good condition. Please note that if there is any overwriting in the quotation, the said item will not be taken in to consideration unless is initialed.

The quotations should be received on or before: - 25/01/2022 on or before 4:00 pm.

The quotation received will be opened on: - 27/01/2022, at 11:00 am.

**NAME OF WORK - Providing concrete platform for New Parking near Main Gate
at GCE, Karad**


SUMMARY SHEET

Sr. No.	Item Description	Amount
1	Work Portion	233613.00
	ADD GST 12%	28033.56
	TOTAL WITH GST	261646.56
	Say	261647.00

NAME OF WORK - Providing concrete platform for New Parking near Main Gate at GCE, Karad

Abstract Sheet

Sr. No.	SSR 21-22 Item No.	Item Description	Qty	Unit	Rate	Amount
1	21.02 Pg. No. 115	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means	0.82	Cum	193.00	158.26
2	21.06 Pg. No. 115	Excavation for foundation in hard murum including removing the excavated material upto distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m) By Mechanical Means	0.82	Cum	212.00	173.84
3	21.37 Pg. No. 117	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete.	62.50	Cum	550.00	34375.00
4	24.10 Pg. No. 131	Providing and laying Cast in situ/Ready Mix cement concrete in M20 of trap/ granite/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	31.25	Cum	6365.00	198906.25
5		Any other repairs				0.00
						0.00
		TOTAL AMOUNT				233613.35
		SAY				233613.00


Principal
Government College of Engineering, Karad