



Phone. No. (02164) 272414, 8275706613
Web : <http://gcekarad.ac.in>
Email: principal@gcekarad.ac.in,
principal.gcekarad@dtmaharashtra.gov.in



Govt. of Maharashtra
GOVT. COLLEGE OF ENGINEERING, KARAD
(An Autonomous Institute of Govt. of Maharashtra)
Vidyanagar, Karad -415124 Dist.- Satara

GCEK/QUOT/Chambers & Gutter near Parking/2022-23/ 4329

Date: 3 DEC 2022

To,

Sub: - Constructing chambers, gutter and laying concrete in front of two-wheeler parking at GCE, Karad

Dear Sir,

With reference to the above, I request you to please quote your most comparative rates for the work as detailed overleaf/enclosed so as to reach the office **on or before 14/12/2022**. The prices of the **work should be quoted F.O.R. at G.C.E., KARAD** and exclusive of all taxes. The delivery period should be stated clearly and adhered to 'AF' or 'D' forms will be supplied where necessary. The R.R. through Bank or V.P. will not be accepted if order is placed. The specification of the material should be mentioned in full such as brand, make and company etc. I do not bind myself to accept/reject the offer, and its detailed leaflet must be attached. Your quotation should be valid at least for 30 days from the date of opening. The quotations should be sent in a sealed envelope. The envelope should please be superscripted with words **'QUOTATION DUE ON – Principal, Govt. College of Engg. Karad'**

With this office reference no. & date of opening should also be mentioned on the sealed envelope. If the materials are not supplied according to the specification, it will be returned to you at your own cost. If ordered, you will have to submit three copies of the bill, which will be passed after receipt of material in good condition. Please note that if there is any overwriting in the quotation, the said item will not be taken in to consideration unless is initialed.

Government registered contractors are only eligible to fill the quotations.

The quotations should be received on or before: - 14/12/2022 on or before 3:00 pm.

The quotation received will be opened on: - 15/12/2022 after 11.00 am.

‘QUOTATION – Principal, Govt. College of Engg. Karad’

Name of Work: - Constructing chambers, gutter and laying concrete in front of two-wheeler parking at GCE, Karad


SUMMARY SHEET

Sr. No.	Description	Amount
	Total Civil Work	Rs. 2,28,318.00
	Add GST 18%	Rs. 41,097.00
	Total with GST	Rs. 2,69,415.00

ABSTRACT (As per SSR 2022-23)

Sr. No.	Item Ref.	Item Description	Qty	Unit	Rate in Rupees	Amount
1	21.01 Pg. No. 153	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m.) By Manual Means.	9.36	Cum	239.00	2237.04
2	21.05 Pg. No. 153	Excavation for foundation in hard murum including removing the excavated material upto distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m) By Manual Means.	8.10	Cum	365.00	2956.50
3	24.08 Pg. No. 176	Providing and laying Cast in situ/ Ready Mix cement concrete in M15 of trap/ granite/ quartzite/ gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honey combed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honey combed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	8.50	Cum	6359.00	54051.50
4	25.11 Pg. No. 177	Providing and laying in situ /Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. including bailing out water, Steel centering formwork, laying/pumping cover blocks, compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	1.30	Cum	7104.00	9235.20

Sr. No.	Item Ref.	Item Description	Qty	Unit	Rate in Rupees	Amount
5	26.17 Pg. No. 185	Providing and laying Cast in situ/Ready Mix cement concrete in M-20 of trap/ granite/ quartzite/ gneiss metal for R.C.C. pardi of required thickness including steel centering, formwork, cover blocks, laying/pumping, compacting , curing , finishing and rougheningthem if special finish is to be provided and curing complete.(Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	1.80	Cum	15567.00	28020.60
6	26.33 Pg. No. 188	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.	0.177	MT	89703.00	15877.43
7	42.12 Pg. No. 275	Providing and constructing Brick Masonry Inspection Chamber 60cm x 45cm x 90cm including 1:4:8 cement concrete foundation 1:2:4 cement concrete channels half round G.S.W. pipes, Brick Masonry, plastering from inside and with frame fixed in cement concrete with R.C.C. Cover medium duty 140 Kilogram with frame etc complete.	4.00	No.	9160.00	36640.00
8	50.85 Pg. No. 351	Providing and fixing Ductile iron Man Hole Covers/ Strom Water Grating and Grating with frame of Various sizes, weight and types and load bearing capacity as per EN-124, equivalent NECO with prior approval of concerned Superintending Engineer.	220.0 0	Kg	288.00	63360.00
9	42.08 Pg. No. 274	Providing and laying concrete pipes of I.S.NP. class of 225mm diameter in proper line, level and slope including necessary collars, excavation, laying, fixing with collars in cement mortar 1:1 and refilling the trench complete.	19.50	Rmt	561.00	10939.50
10		Other repairs works if any		LS		5000.00
		TOTAL AMOUNT				228317.77
		SAY				228318.00


Principal,
Govt. College of Engineering, Karad