



Phone. No. (02164) 272414, 8275706613
Web : <http://gcekarad.ac.in>
Email: principal@gcekarad.ac.in,
principal.gcekarad@dtmaharashtra.gov.in



Govt. of Maharashtra
**GOVT. COLLEGE OF ENGINEERING,
KARAD**

(An Autonomous Institute of Govt. of Maharashtra)
Vidyanagar, Karad -415124 Dist.- Satara

GCEK/QUOT/Concrete Coba(SAE club & compressor)/2021-22/186

Date:-

14 JAN 2022

To,

Sub: - Preparing platform in concrete coba behind workshop for SAE club, compressor machine, grinder & solar panel at GCE, Karad

Dear Sir,

With reference to the above, I request you to please quote your most comparative rates for the work as detailed overleaf/enclosed so as to reach the office **on or before 24/01/2022**. The prices of the work should be quoted F.O.R. at G.C.E., KARAD and exclusive of all taxes. The delivery period should be stated clearly and adhered to 'AF' or 'D' forms will be supplied where necessary. The R.R. through Bank or V.P. will not be accepted if order is placed. The specification of the material should be mentioned in full such as brand, make and company etc. I do not bind myself to accept/reject the offer, and its detailed leaflet must be attached. Your quotation should be valid at least for 30 days from the date of opening. The quotations should be sent in a sealed envelope. The envelope should please be superscripted with words **'QUOTATION DUE ON – Principal, Govt. College of Engg. Karad'**

With this office reference no. & date of opening should also be mentioned on the sealed envelope. If the materials are not supplied according to the specification, it will be returned to you at your own cost. If ordered, you will have to submit three copies of the bill, which will be passed after receipt of material in good condition. Please note that if there is any overwriting in the quotation, the said item will not be taken in to consideration unless is initialed.

The quotations should be received on or before: - 24/01/2022 on or before 4:00 pm.

The quotation received will be opened on: - 25/01/2022, at 11.00 am.

‘QUOTATION – Principal, Govt. College of Engg. Karad’

**Name of Work: - Preparing platform in concrete coba behind workshop for SAE club,
Compressor machine, grinder & solar panel at GCE, Karad**

SUMMARY SHEET

Sr. No.	Description	Amount
	Total Civil Work	Rs. 1,52,219.00
	Add GST 12%	Rs. 18,266.00
	Total with GST	Rs. 1,70,485.00

ABSTRACT (As per SSR 2021-22)

Sr. No.	Item Ref.	Item Description	Qty	Unit	Rate in Rupees	Amount
1	21.01 Pg. No. 115	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m.) By Manual Means	5.54	Cum	232.00	1285.28
2	21.37 Pg. No. 117	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete.	14.63	Cum	550.00	8046.50
3	24.08 Pg. No. 131	Providing and laying Cast in situ/ Ready Mix cement concrete in M15 of trap/ granite/ quartzite/ gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honey combed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honey combed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	17.87	Cum	6030.00	107756.10
4	27.12 Pg. No. 144	Providing fly ash brick masonry with conventional/ I.S. type fly ash bricks in C.M. 1:6 in foundation and plinth including bailing out water manually striking joints, racking out joints watering and scaffolding etc. complete. Completed Item Rate = 6762/ Cum Fly Ash Brick = (500 x 7) = 3500/ Cum Total Rate without brick = 3262/ Cum	5.66	Cum	3262.00	18462.92

Sr. No.	Item Ref.	Item Description	Qty	Unit	Rate in Rupees	Amount
5	32.11 Pg. No. 153	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 Kilogram per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc. complete.	19.48	Sqm	599.00	11668.52
6		Other repairs works if any		LS		5000.00
		TOTAL AMOUNT				152219.32
		SAY				152219.00



Principal

Govt. College of Engineering, Karad.