



Phone. No. (02164) 272414, 8275706613
Web : <http://gcekarad.ac.in>
Email: principal@gcekarad.ac.in,
principal.gcekarad@dtmaharashtra.gov.in



Govt. of Maharashtra
**GOVT. COLLEGE OF ENGINEERING,
KARAD**

(An Autonomous Institute of Govt. of Maharashtra)
Vidyanagar, Karad -415124 Dist.- Satara

GCEK/QUOT/PG Hostel Refurbishment/2020-21/84)

Date:- 11 1 FEB 2021

To,

Sub: - Refurbishment of PG Hostel at GCE, Karad

Dear Sir,

With reference to the above, I request you to please quote your most comparative rates for the work as detailed overleaf/enclosed so as to reach the office **on or before 22/02/2021**. The prices of the **work should be quoted F.O.R. at G.C.E., KARAD** and exclusive of all taxes. The delivery period should be stated clearly and adhered to 'AF' or 'D' forms will be supplied where necessary. The R.R. through Bank or V.P. will not be accepted if order is placed. The specification of the material should be mentioned in full such as brand, make and company etc. I do not bind myself to accept/reject the offer, and its detailed leaflet must be attached. Your quotation should be valid at least for 30 days from the date of opening. The quotations should be sent in a sealed envelope. The envelope should please be superscripted with words **'QUOTATION DUE ON – Principal, Govt. College of Engg. Karad'**

With this office reference no. & date of opening should also be mentioned on the sealed envelope. If the materials are not supplied according to the specification, it will be returned to you at your own cost. If ordered, you will have to submit three copies of the bill, which will be passed after receipt of material in good condition. Please note that if there is any overwriting in the quotation, the said item will not be taken in to consideration unless is initialed.

The quotations should be received on or before: - 22/02/2021 on or before 4:00 pm.

The quotation received will be opened on: - 23/02/2021

‘QUOTATION – Principal, Govt. College of Engg. Karad’

Name of Work: - Refurbishment of PG Hostel at GCE, Karad

SUMMARY SHEET

Sr. No.	Description	Amount
1	Work Portion	Rs. 2,25,482.00
	Add GST 12%	Rs. 27057.84
	Total with GST	Rs. 2,52,539.84
	SAY TOTAL	Rs. 2,52,540.00

ABSTRACT (As per SSR 2020-21)

NAME OF WORK - Refurbishment of PG Hostel at GCE, Karad						
Sr. No.	Item Ref.	Item Description	Qty	Unit	Rate in Rupees	Amount
1	32.33 Pg. No. 203	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete.	49.10	Sqm	47.00	2307.70
2	21.05 Pg. No. 148	Excavation for foundation in hard murum including removing the excavated material upto distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m) By Manual Means	4.31	Cum	331.00	1426.61
3	21.36 Pg. No. 152	Filling in plinth and floors with approved excavated material in 15cm. to 20cm. Layers including watering and compacting etc. complete.	23.90	Cum	109.00	2605.10
4	24.08 Pg. No. 169	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/granite/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	24.77	Cum	5936.00	147034.72

Sr. No.	Item Ref.	Item Description	Qty	Unit	Rate in Rupees	Amount
5	27.12 Pg. No. 190	Providing fly ash brick masonry with conventional / I.S. type fly ash bricks in C.M. 1:6 in foundation and plinth including bailing out water manually striking joints, racking out joints watering and scaffolding etc. complete.	2.80	Cum	6082.00	17029.60
6	32.12 Pg. No. 201	Providing rough cast cement plaster externally in two coats to concrete, brick or stone masonry surfaces in all positions with base coat of 12 to 15 mm thick in C.M. 1:4 and rough cast treatment 12mm thick in proportion 1:1 1/2:3 including scaffolding and fourteen days curing complete.	57.22	Sqm	529.00	30269.38
7	33.17 Pg. No. 207	Providing and laying machine cut machine polished shahabad Stone slabs 20 to 25mm thick for treads and risers of steps and staircases, with rounded nosing for the treads on a bed of 1:4 cement mortar including cement float, filling joints with neat cement slurry, curing, polishing and cleaning etc. complete.	4.50	Sqm	1026.00	4617.00
8	33.20 Pg. No. 207	Providing sills of polished Kadappa stone 25mm to 30mm thick, on a bed of 1:4 cement mortar including cement float, filling joints with slurry, curing polishing and cleaning etc. complete.	9.00	Sqm	1010.00	9090.00
9	33.21 Pg. No. 207	Providing sills of required material 20mm to 25mm thick, on a bed of cement mortar 1:4 including cement float, filling joints with neat cement slurry, curing, polishing, moulding edges, cleaning complete. a) Marble other than white makrana	3.00	Sqm	2034.00	6102.00
10		Other repairs works if any		LS		5000.00
		TOTAL AMOUNT				225482.11


Principal

Govt. College of Engineering, Karad.