



Phone. No. (02164) 272414, 8275706613  
Web : <http://gcekarad.ac.in>  
Email: [principal@gcekarad.ac.in](mailto:principal@gcekarad.ac.in),  
[principal.gcekarad@dtmaharashtra.gov.in](mailto:principal.gcekarad@dtmaharashtra.gov.in)

Govt. of Maharashtra  
**GOVT. COLLEGE OF ENGINEERING, KARAD**  
(An Autonomous Institute of Govt. of Maharashtra)  
Vidyanagar, Karad -415124 Dist.- Satara

GCEK/QUOT/STP\_Water Tank/2022-23/1245

Date:- 23 MAR 2023

To,

**Sub: - Construction of Water tank for STP at GCE, Karad**

Dear Sir,

With reference to the above, I request you to please quote your most comparative rates for the work as detailed overleaf/enclosed so as to reach the office **on or before 31/03/2023**. The prices of the **work should be quoted F.O.R. at G.C.E., KARAD** and exclusive of all taxes. The delivery period should be stated clearly and adhered to 'AF' or 'D' forms will be supplied where necessary. The R.R. through Bank or V.P. will not be accepted if order is placed. The specification of the material should be mentioned in full such as brand, make and company etc. I do not bind myself to accept/reject the offer, and its detailed leaflet must be attached. Your quotation should be valid at least for 30 days from the date of opening. The quotations should be sent in a sealed envelope. The envelope should please be superscripted with words **'QUOTATION DUE ON – Principal, Govt. College of Engg. Karad'**

With this office reference no. & date of opening should also be mentioned on the sealed envelope. If the materials are not supplied according to the specification, it will be returned to you at your own cost. If ordered, you will have to submit three copies of the bill, which will be passed after receipt of material in good condition. Please note that if there is any overwriting in the quotation, the said item will not be taken in to consideration unless is initialed.

**Government registered contractors are only eligible to fill the quotations.**

**The quotations should be received on or before: - 31/03/2023 on or before 3:00 pm.**

**The quotation received will be opened on: - 01/04/2023 after 11.00 am.**

**‘QUOTATION – Principal, Govt. College of Engg. Karad’**

**Name of Work: - Construction of Water tank for STP at GCE, Karad**


**SUMMARY SHEET**

<b>Sr. No.</b>	<b>Description</b>	<b>Amount</b>
	<b>Total Civil Work</b>	<b>Rs. 83,549.00</b>
	Add GST 18%	Rs. 15,039.00
	<b>Total with GST</b>	<b>Rs. 98,588.00</b>

**ABSTRACT (As per SSR 2022-23)**

<b>Sr. No.</b>	<b>Item Ref.</b>	<b>Item Description</b>	<b>Qty</b>	<b>Unit</b>	<b>Rate in Rupees</b>	<b>Amount</b>
1	21.36 Pg. No. 157	Filling in plinth and floors with approved excavated material in 15cm. to 20cm. Layers including watering and compacting etc. complete.	22.22	Cum	120.00	2666.40
2	25.11 Pg. No. 178	Providing and laying in situ/ Ready Mix cement concrete M-20 of trap/ granite/ quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. including bailing out water, Steel centering formwork, laying/ pumping cover blocks, compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	1.59	Cum	7104.00	11295.36
3	25.70 Pg. No. 182	Providing and laying Cast in situ/ Ready Mix cement concrete M-20 of trap/ granite/ quartzite/ gneiss metal for R.C.C. slabs and landings as per detailed designs and drawings including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete,(Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	1.05	Cum	13932.00	14628.60
4	27.12 Pg. No. 198	Providing fly ash brick masonry with conventional/ I.S. type fly ash bricks in C.M. 1:6 in foundation and plinth including bailing out water manually striking joints, racking out joints watering and scaffolding etc. complete.	4.27	Cum	6884.00	29394.68
5	31.06 Pg. No. 205	Providing waterproof plaster in W.C. and bath 12 mm thick for dado in cement mortar 1:3 with neat finishing, floating using waterproofing compound at the rate of 1 Kilogram. per bag of cement of approved make and manufacturer and curing etc. complete. (Excluding Tiles) (As directed by Engineer in Charge)	17.00	Sqm	387.00	6579.00

Sr. No.	Item Ref.	Item Description	Qty	Unit	Rate in Rupees	Amount
6	32.11 Pg. No. 209	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 Kilogram per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc. complete.	20.13	Sqm	639.00	12863.07
7	42.08 Pg. No. 274	Providing and laying concrete pipes of I.S.NP. class of 225mm diameter in proper line, level and slope including necessary collars, excavation, laying, fixing with collars in cement mortar 1:1 and refilling the trench complete.	2.00	Rmt	561.00	1122.00
8		Other works if any (such as labour charges for steel cutting, steel jali, etc.)		LS		5000.00
		<b>TOTAL AMOUNT</b>				<b>83549.11</b>
		<b>SAY</b>				<b>83549.00</b>

  
**Principal,**  
**Govt. College of Engineering, Karad**