

Recall 1st Attempt -



GOVERNMENT COLLEGE OF ENGINEERING, KARAD.
Vidyanagar, Karad 415 124. Tal: Karad, Dist: Satara, Maharashtra, India.

Phone No. : (02164) 274066, 271711, 272414, 272415) Fax No. : (02164)
271713 Email: gcek_brns@yahoo.co.in

No. CEK/QUOT/Shifting Of Shed/2019-20/94

Date:- 28/02/2019

To,

**Sub: - Fixing of Electrical & Mechanical Shed Behind Workshop Area At Gce
Karad.**

Dear Sir,

With reference to the above, I request you to please quote your most comparative rates for the work as detailed overleaf/enclosed so as to reach the office **on or before 04/03/2019**. The prices of the **work should be quoted F.O.R. at G.C.E., KARAD** and exclusive of all taxes. The R.R. through Bank or V.P. will not be accepted if order is placed. The specification of the work should be mentioned in full such as brand, make and company etc. I do not bind myself to accept/reject the offer, and its detailed leaflet must be attached. Your quotation should be valid at least for 30 days from the date of opening. The quotations should be sent in a sealed envelope. The envelope should please be superscripted with words **'QUOTATION DUE ON – Principal, Govt. College of Engg. Karad'**

With this office reference No. & date of opening should also be mentioned on the sealed envelope. If the materials are not supplied according to the specification, it will be returned to you at your own cost. If ordered, you will have to submit three copies of the bill, which will be passed after receipt of material in good condition. Please note that if there is any overwriting in the quotation, the said item will not be taken in to consideration unless is initialed.

The quotations should be received on or before: - 04/03/2019 on or before 4-00 pm.

The quotation received will be opened on: - 04/03/2019, at 5-00 pm.

'QUOTATION – Principal, Govt. College of Engg. Karad'

RECAPITULATION SHEET

**Name Of Work : Fixing of Electrical & Mechanical Shed Behind Workshop
Area**

	Description	Amount Rs.
1	Civil Work (Detail Estimate Enclosed) RS	266058.21
2	Add 12% GST RS	31,926.99
3	Total with GST RS.	2,97,985.20
	SAY RS.	2,97,986.00


**Name Of Work : Fixing of Electrical & Mechanical Shed Behind Workshop
Area At Gce Karad.**

Sr. No.	Original Description of Items	Qty	Unit	Rate	Amount
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means	10.95	Cum	143.00	1565.85
2	Excavation for foundation in hard murum including removing the excavated material upto distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50m) By Mechanical Means	2.59	Cum	157.00	406.63

3	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	18.30	Cum	4,257.00	77903.10
4	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete.	33.28	Cum	378.00	12579.84
5	Providing second class Burnt Brick masonry with conventional/ I.S.type bricks in cement mortar 1:6 in plinth as backing in composite masonry including bailing out water manually, striking joints, raking out joints and watering etc Complete	5.25	Cum	4,973.00	26108.25
6	Providing and laying Cast in situ/Ready Mix cement concrete in M20 of gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	1.46	cum	5,028.00	7340.88
7	Providing structural steel work in single stanchions composed of R.S.J.Channel etc. with caps, bases, mild steel plated, angle brackets, cleats, gusset plates, anchor bolts etc. as per detailed designs and drawings or as directed including cutting, fabrication, hoisting, erecting fixing in position, making riveted/ bolted/ welded connection and one coat of anticorrosive paint and over it two coats of oil painting approved quality and shade etc. complete	1.27	M.T	10,061.00	12777.47

8	Providing structural steel work in single stanchions composed of R.S.J.Channel etc. with caps, bases, mild steel plated, angle brackets, cleats,gusset plates, anchor bolts etc. as per detailed designs and drawings or as directed including cutting, fabrication, hoisting, erecting fixing in position, making riveted/ bolted/ welded connection and one coat of anticorrosive paint and over it two. coats of oil painting approved quality and shade etc. complete.	0.05	M.T	68,325.00	3689.55
9	Providing and fixing corrugated galvanised iron sheets of 0.63mmthick (24 B.W.G.) for roofing without wind tiles including fastening with galvanised iron screws and bolts, lead and bitumen washers asper drawing etc. complete.(Weight of 5.5 kg/sq.m.).	401.00	Sqm	84.00	33684.00

10	Providing and fixing corrugated galvanised iron sheets of 0.63mmthick (24 B.W.G.) for roofing without wind tiles including fastening with galvanised iron screws and bolts, lead and bitumen washers asper drawing etc. complete.(Weight of 5.5 kg/sq.m.).	37.00	Sqm	686.00	25382.00
11	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.	44.08	Sqm	608.00	26800.64
12	Providing and applying two coats of lead/zinc base oil paint/bituminious paint of approved colour to new structural steel work and iron work in buildings including scaffolding if necessary, cleaning and preparing the surface etc. complete			lumpsum	8000.00
13	Providing and fixing all types of screws,nuts bolts fixtures with all lead lifts completely etc.			lumpsum	2000.00
14	Providing and fixing crimped with G.I. mesh and size 20 mm x 20mm10 guage to iron angle frame including welding crimp mesh to angleframe and steel flat, fixing the frame in its original position and oilpainting etc.complete (excluding cost of structural steel)	52.00	Sqm	535	27820.00
				Total	266058.21


28/10/2012
Principal

Govt. College of Engineering, Karad.